

# Coronavirus (COVID-19) Domestic Installation Working Methodology

#### Contents

Leaving your residence	2
Travelling with your colleague	2
Stopping for fuel/food/water	2
Travelling to the warehouse/local hub	3
Warehouse Facilities	3
Kit collection	3
Travelling to the site	3
Arrival at site	4
Introduction to customer	4
Erect access equipment	4
Property checks/assessment – Internal	4
Property assessment – External	
Installation setup	5
Commencing Internal Works	6
Commencing External Works	6
Transporting and Fitting Solar Panels	6
Completing Internal Works and Commissioning	7
Install Complete	7
Customer Handover	8
Leaving the Property	8
Stop for fuel/food/water	9
Travelling to the warehouse/local hub	9
Waste Disposal	9
Travelling with your colleague	9
Arriving at Your Residence	9



#### **Leaving your residence**

- a) Is anyone in your residence showing signs of Coronavirus (COVID-19), if yes inform your TM and HR immediately.
- b) Before departing use sanitising/anti-bacterial wipes to clean all hard surfaces within the cab of the vehicle.
- c) Use sanitising/anti-bacterial wipes/gel on hands/forearms if exposed.
- d) Ensure all used sanitising/anti-bacterial wipes have been securely bagged for disposal.

## Travelling with your colleague

- a) Before entering the vehicle ensure the intended passenger has used sanitising/anti-bacterial wipes/gel on hands/forearms if exposed.
- b) Both operatives put on face coverings.
- c) Open windows (if appropriate) allowing a steady flow of fresh air.
- d) Touch the least number of surfaces as possible.

# Stopping for fuel/food/water

- a) Follow social distancing guidelines wherever possible. In the event of not being able to adhere to the guidance, the use of a face covering should be considered.
- b) Use disposable gloves when handling fuel pumps. Discard in onsite bins when task completed.
- c) Use contactless payment where possible.
- d) \*Recommendation\* Where possible bring pre-prepared food and drinks, to avoid unnecessary stops.



## Travelling to the warehouse/local hub

a) You must call the Warehouse Manager (WM) 15 minutes before arrival. WM will advise on collection status and prepare goods.

#### **Warehouse Facilities**

- a) Entrance to the warehouse is strictly prohibited. Should access be required, prior agreement with Warehouse Manager and/or Project Manager must be sought.
- b) Welfare facilities are available, with access limited to 1 team having use at any time.
- c) Operatives must always follow designated walkways.
- d) Hands must be washed before and after using any welfare facilities.
- e) Touch the least number of surfaces as possible.
- f) Doors are to be left open and should not be closed by any other person than WM.

#### Kit collection

- a) Entrance to the warehouse is strictly prohibited.
- b) WM will allocate a collection point and time on the pre arrival call.
- c) Follow social distancing guidelines wherever possible. In the event of not being able to adhere to the guidance, the use of a face covering should be considered.
- d) Use disposable gloves when handling materials/equipment. Discard in onsite bins when task completed.
- e) WM to use sanitising/anti-bacterial wipes on cages before and after team have unloaded materials/equipment.

# Travelling to the site

- a) Both operatives put on face coverings.
- b) Open windows (if appropriate) allowing a steady flow of fresh air.
- c) Touch the least number of surfaces as possible.
- d) Call customer to give ETA and recap on process for entering property and safe systems of work, escalating any concerns to TM if needed.



#### **Arrival at site**

a) External assessment of the property to be undertaken where possible without accessing the grounds of the property, escalating any concerns to TM if needed.

#### Introduction to customer

- a) Use disposable gloves before proceeding to have any contact with customer property including external gates, doorbells etc.
- b) Knock on door and immediately step back a minimum of 2m.
- c) Recap on process for entering property and safe systems of work, escalating any concerns to TM if needed.
- d) PPE must be worn before entering the property, this includes but not limited to;
  - Disposable gloves
  - Disposable coveralls
  - > Face covering
  - Overshoes

# **Erect access equipment**

- a) Set up safety exclusion zone.
- b) Move all required equipment within working area.
- c) All equipment should be erected in line with GET-UK RAMS.

# Property checks/assessment - Internal

- a) PPE must be worn when entering the property (in order of fitting)
  - Disposable coverall
  - Shoe covers
  - Face covering
  - Goggles/face shield (if required)
  - Disposable gloves
- b) Follow social distancing guidelines wherever possible.
- c) Doors should always remain open.
- d) Assess the equipment within the immediate working area, ensuring no defects or damage are present, which may result in postponement of the install or harm/injury to any person(s), escalating any concerns to TM if needed.



- e) Assess the area(s) where the work will take place, taking note of required tools/material to undertake task.
- f) When exiting the property, PPE must be removed (in order of removal)
  - Gloves.
    - Grip the outside of the glove with the opposite gloved hand, peel off.
    - Hold the removed glove in the gloved hand.
    - ♣ Slide the fingers of the un-gloved hand under the remaining glove at the wrist.
    - Peel the second glove off over the first glove.
    - Bag ready for disposal.
  - Coverall.
    - Unfasten.
    - ♣ Pull down away from neck and shoulders touching inside only.
    - ♣ Pull down over legs.
    - Fold or roll into a bundle.
    - Bag ready for disposal.
  - Goggles/face shield (if worn)
    - Handle only by the headband or the sides.
    - Bag separately ready for cleaning/sanitising.
  - > Face covering
    - Unfasten the ties or strap.
    - Pull away from face without touching front of the covering.
    - Bag ready for disposal.


# Property assessment – External

- a) Standard PPE to worn at all times.
- b) Follow social distancing guidelines wherever possible.
- d) All checks should be completed in line with GET-UK installation process.

## **Installation setup**

- a) Ensure all required tools/equipment are in the safety exclusion zone, alleviating the need to make multiple trips off the premise to the vehicle.
- b) Prepare equipment outside within exclusion zone to reduce time spent within the property.
  - Fit AC/DC isolators to inverter back board.
  - Mount inverter bracket to back board.
  - Terminate DC isolator and MC4 connectors.





- ♣ Remove knockouts from PVDB and install glands.
- ♣ Terminate meter tails and earth connection in PVDB.

## **Commencing Internal Works**

- a) PPE must be worn when entering the property (in order of fitting)
  - > Disposable coverall
  - Shoe covers
  - Face covering
  - Googles/face shield (if required)
  - Disposable gloves
- b) Follow social distancing guidelines wherever possible.
- c) Aim to complete works in one area of the property at a time, to limit movement and avoid interaction with others.
- d) Wipe down immediate working area with sanitising/anti-bacterial wipes, before commencing works, bagging ready for disposal.
- e) Do not put any tools or equipment near your face.
- f) Do not leave any tools or equipment unattended.
- g) Wipe down immediate working area with sanitising/anti-bacterial wipes, after completing works, bagging ready for disposal.

# **Commencing External Works**

- a) Follow social distancing guidelines wherever possible.
- b) All works should be completed in line with GET-UK installation process.

# **Transporting and Fitting Solar Panels**

- a) Electrician will be required to exit the property to assist.
- b) Do not leave any tools or equipment unattended within the property.
- c) PPE must be removed (in order of removal).
  - Gloves.
    - Grip the outside of the glove with the opposite gloved hand, peel off.
    - Hold the removed glove in the gloved hand.
    - Slide the fingers of the un-gloved hand under the remaining glove at the wrist.
    - Peel the second glove off over the first glove.
    - Bag ready for disposal.



- Coverall
  - Unfasten.
  - ♣ Pull down away from neck and shoulders touching inside only.
  - Pull down over legs.
  - Fold or roll into a bundle.
  - Bag ready for disposal.
- Goggles/face shield (if worn)
  - Handle only by the headband or the sides.
  - Bag separately ready for cleaning/sanitising.
- Face covering
  - Unfasten the ties or strap.
  - Pull away from face without touching front of the covering.
  - Bag ready for disposal.
- d) Follow social distancing guidelines wherever possible.
- e) Disposable gloves must be worn.
- f) All works should be in line with GET-UK installation process.

#### **Completing Internal Works and Commissioning**

- a) PPE must be worn when entering the property (in order of fitting)
  - Disposable coverall
  - Shoe covers
  - > Face covering
  - Googles/face shield (if required)
  - Disposable gloves
- b) Follow social distancing guidelines wherever possible.
- c) Aim to complete works in one area of the property at a time, to limit movement and avoid interaction with others.
- d) Should the roofer be required to assist internally, PPE must be worn and same process applies (17.a).
- e) Any occupants must be made aware of a second operative within property.
- f) All works should be completed in line with GET-UK installation process.

# **Install Complete**

- a) All tools, excess and waste material must be cleared from within the property, starting at the furthest most point to avoid re-entry.
- b) Wipe all touched surfaces with sanitising/anti-bacterial wipes, after clearing area, bagging ready for disposal.
- c) All waste to be put in safety exclusion zone.



- d) Ask customer to check works completed are to satisfactory standard, to ascertain whether further access is required.
- e) PPE must be removed (in order of removal).
  - Gloves.
    - Grip the outside of the glove with the opposite gloved hand, peel off
    - Hold the removed glove in the gloved hand.
    - ♣ Slide the fingers of the un-gloved hand under the remaining glove at the wrist.
    - Peel the second glove off over the first glove.
    - Bag ready for disposal.
  - Coverall
    - Unfasten.
    - ♣ Pull down away from neck and shoulders touching inside only.
    - Pull down over legs.
    - Fold or roll into a bundle.
    - Bag ready for disposal.
  - Goggles/face shield (if worn)
    - Handle only by the headband or the sides.
    - Bag separately ready for cleaning/sanitising.
  - > Face covering
    - Unfasten the ties or strap.
    - Pull away from face without touching front of the covering.
    - Bag ready for disposal.
- f) Wipe hands with sanitising/anti-bacterial wipes/gel.
- g) Put on disposable gloves.
- h) All tools/material/equipment and waste to be put into the van.

#### **Customer Handover**

- a) Handover should be performed externally where possible.
- b) Follow social distancing guidelines wherever possible.

# **Leaving the Property**

- a) All PPE must be removed and bagged for disposal.
- b) Wipe hands with sanitising/anti-bacterial wipes/gel.
- c) Both operatives put on face covering.
- d) Open windows (if appropriate) allowing a steady flow of fresh air.
- e) Touch the least number of surfaces as possible.



# Stop for fuel/food/water

- a) Follow social distancing guidelines wherever possible. In the event of not being able to adhere to the guidance, the use of a face covering should be considered.
- b) Use disposable gloves when handling fuel pumps. Discard in onsite bins when task completed.
- c) Use contactless payment where possible.

## Travelling to the warehouse/local hub

- a) You must call the Warehouse Manager (WM) 15 minutes before arrival. WM will advise on delivery status and unloading bay.
- b) Warehouse/local hub rules apply (see 5 a-f)

## **Waste Disposal**

- a) WM will identify correct waste disposal unit(s).
- b) Both operatives put on disposable gloves.
- c) all waste to be placed directly into assigned skips/disposal units.
- d) All tools/equipment to be cleaned using sanitising/antibacterial wipes.
- e) Remove all PPE and dispose in appropriate bin(s).

# Travelling with your colleague

- a) Before entering the vehicle ensure both operatives have used sanitising/antibacterial wipes/gel on hands/forearms if exposed.
- b) Both operatives put on face coverings.
- c) Open windows (if appropriate) allowing a steady flow of fresh air.
- d) Touch the least number of surfaces as possible.

# **Arriving at Your Residence.**

- a) Use sanitising/anti-bacterial wipes to clean all hard surfaces within the cab of the vehicle.
- b) Use sanitising/anti-bacterial wipes/gel on hands/forearms if exposed.
- c) Ensure all used sanitising/anti-bacterial wipes have been securely bagged for disposal.
  - Recommendation; Workwear i.e. Clothing to be removed and washed as soon as possible once entering the property.



